

**DR. BABASAHEB AMBEDKAR MARATHWADA UNIVERSITY,  
AURANGABAD – 431 004, Maharashtra State (India)**

NAAC – Accredited A

UNIVERSITY CAMPUS  
AURANGABAD-431004  
(Maharashtra) INDIA

EPABX > (0240) 2403397 to 400  
Off. Tele > (0240) 2403104 to 106  
Registrar > (Offi.) (0240) 2403333  
(Resi.) (0240) 2400203  
Fax > (0240) 2403113 / 2403335  
Web Site > www.bamu.net  
E-mail > vc@bamu.net  
E-mail > registrar@bamu.net



Ref. No. UE/TA/2021-22/

Date: - 31/08/2021

**INVITATION OF QUOTATIONS IN TWO BIDS SYSTEMS**  
**(Last Date for Submission 06 - 10 -2021)**

To, \_\_\_\_\_  
M/s: \_\_\_\_\_

**Name Of work: - Consideration of the proposal of Changing the Roofing Sheets of Tower of UNIC Dept. in the premises of Dr. Babasaheb Ambedkar Marathwada University.**

The Terms & Conditions on the reverse should be read carefully and noted in order to comply with.

SCHEDULE-B					
Item No.	Description	Qty	Unit	Rate	Amount
1	Providing and fixing plain zinc sheeting of 0.80 mm thick (22 B.W.G.) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt galvanised iron screws and bolts, lead and bitumen washers etc. complete.(Weight of 6.8 kg/sq.m.).	43.67	SQ.M	1083.10	47298.98
2	Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete.	0.160	M.T	96277.46	15404.39
3	Removing G.I. or A.C. sheet roofing including purlins, principal rafters etc. including sorting serviceable and unserviceable materials, stacking the same as and where directed in the compound including scaffolding etc. complete.	42.60	SQ.M	85.98	3662.75
4	Dismantling brick masonry in lime or cement mortar and stacking the materils as directed with all leads, lifts etc.	2.96	CUM	319.79	946.58
5	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	2.96	CUM	7734.49	22894.08
6	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to	32.64	SQ.M	647.87	21146.48

	receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. Complete.				
7	Providing and applying two coats of exterior white weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface ,applying primer coat ,scaffolding if necessary, and watering the surface for two days etc complete. NOTE: For Item No. 15 to 18 prior approval of Superintending Engineer will be necessary.	32.64	SQ.M	226.48	7392.31
8	Providing cement based water proofing treatment to terraces (Indian water proofing or alike) with brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M.1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer for 3 days, applying cement slurry over this layer joints of brick bats with C.M.1:3 admixed with approved water proofing compound and finally top finishing with average 20 mm. thick layers of same mortar added with jute fiber at 1Kilogramper bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Marking finished surface with false squares of 300mm x 300 mm. making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet and curing and covering 10 years Guarantee against leak proof ness on Court fee stamp paper of Rs. 500/- including ponding test etc. complete.	25.25	SQ.M	1189.92	30045.48
9	Royalty against extraction of material such as metal, sand, murum, rubble, etc. for construction work.	3.79	CUM	141.34	535.94
	<b>Estimated Cost</b>				<b>149326.98</b>
	<b>Say</b>				<b>149327</b>

- sd -  
Registrar

## TERMS AND CONDITIONS

1. The quotation should be addressed to Registrar, Dr. Babasaheb Ambedkar Marathwada University, Aurangabad.
2. The Contractor should provide following document at the time of submission of Quotation:-

### **(A) ENVELOPE NO. 1 DOCUMENTS)**

The first envelope "Envelope No.1" shall contain the following documents of civil contractor.

- i. The Earnest Money Deposit shall be paid via Demand Draft mode only. The DD should be enclosed.
  - ii. Copy of Certificate in Original or an attested copy as a registered contractor with (a) State P.W.D. (b) State Irrigation Dept. (c) Maharashtra Jeevan Pradhikaran Authority, (d) Municipal Corporation etc. I M.I.D.C. in appropriate class as may be applicable of civil, valid on the date of submission.
  - iii. Copy of Income tax return assessment FY 2020-21, i.e. AY 2021-22 or bank statement 2020-2021.
  - iv. Copy of pan Card.
  - v. Copy of valid registration certificate under good and service tax Act 2017 or provisional GST No. issued by competent authority. This certificate should be valid on the date of quotation opening.
4. SGST and CGST has been implemented by the respective Govt. with effect from 01/07/2017. So contractor must quote his rate keeping effect of GST in mind & no claims will be accepted by this office in connection to GST later.
  5. The successful bidder has to submit all the supported documents/ bills/ vouchers of the materials brought at site while claiming the bills.
  6. The amount of earnest money will be forfeited, in case a successful contractor does not pay the amount of initial security deposit within the time specified as stipulated by the Registrar and complete the contract documents. In all other cases, earnest money will be refundable.
  7. The security deposit of 5% of quoted cost. The successful bidder must be paid 2.5% Initial security deposit before the work order and Remaining 2.5% Percent to be deducted from bills so as to make the total amount of total security deposit equal to 5% of quoted cost. Security Deposit will not carry any interest.
  8. Dr. Babasaheb Ambedkar Marathwada University, Aurangabad does not bind itself to accept the lowest or any such quotation and has the right to accept or reject whole or any part of tenders or a portion of the work without assigning any reasons. No correspondence in case of rejected tenders will be entertained. Incomplete quotations are liable to be rejected.

All questions, disputes or differences arising under and out of or in connection with the contract, if concluded, shall be referred to the sole arbitrator appointed by the Registrar, Dr. Babasaheb Ambedkar Marathwada University, Aurangabad.