

EPABX : (0240) 2403397 to 400
 Off. Tele : (0240) 2403104 to 106
 Registrar : (Offi.) (0240) 2403333
 (Resi.) (0240) 2400203
 Fax : (0240) 2403113 / 2403335
 Web Site : www.bamu.net
 E-mail : vc@bamu.net
 E-mail : registrar@bamu.net



UNIVERSITY CAMPUS
 Chh. Sambhajinagar-431004
 (Maharashtra) INDIA

Ref. No. UE/TA/2026-27/

Date: - 23/06/2026

INVITATION OF QUOTATIONS IN TWO BIDS SYSTEMS

(Last Date for Submission)

08/07/2026, 3.00 PM

To: _____
 M/s: _____


Name of work: - Construction of UCR Compound wall at Gut No. 45 in the premises of Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar.

The Terms & Conditions on the reverse should be read carefully and noted in order to comply.


SCHEDULE - B

Item No.	Description of Items	Qty.	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Mechanical Means	16.20	Cu.M	217.35	3521.07
2	Excavation for foundation in hard murum including removing the excavated material up to distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	16.20	Cu.M	238.35	3861.27
3	Excavation for foundation in hard murum and boulders including removing the excavated material upto a distance 50 metres, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5m.) By Mechanical Means	8.10	Cu.M	264.60	2143.26
4	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	3.24	Cu.M	1991.55	6452.62
5	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.62	Cu.M	6734.05	10909.16

7	Providing uncoursed rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in superstructure including racking out joints when plastering is to be done / striking joints when no plastering is to be done on inside watering and scaffolding etc.complete.	32.40	Cu.M	6633.76	214933.82
8	Providing flush grooved pointing with cement mortar 1:3 for stone masonry work including scaffolding and curing etc. complete.	86.40	Sq.M	193.67	16733.09
9	Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/ granite/quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Crushed sand VSI Grade).	2.03	Cu.M	7246.25	14709.88
10	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	18.90	Sq.M	699.22	13215.26
11	Royalty against extraction of material such as metal, sand, murum, rubble, etc. for construction work.				
	Royalty of Sand	13.88	Cu.M	237.37	3294.10
	Royalty of Other Material	44.15	Cu.M	216.18	9545.10
	ESTIMATED AMOUNT				299318.64
	Say				299319


J.A.


E.M.


Dy. E.


E.E.


J.E.


Registrar

TERMS AND CONDITIONS

1. The quotation should be addressed to Registrar, Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajnagar & submitted in the office of Executive Engineer, Estate Section, Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajnagar
2. The Contractor should provide following document at the time of submission of Quotation:-

(A) ENVELOPE NO. 1 DOCUMENTS

The first envelope "Envelope No.1" shall contain the following documents.

- vii. **The Earnest Money Deposit** shall be paid via Demand Draft mode only. The DD should be enclosed. **(D.D. of Rs. 3000)**
 - viii. **Copy** of Certificate in Original or an attested copy as a registered contractor with (a) State P.W.D. (b) State Irrigation Dept. (c) Maharashtra Jeevan Pradhikaran Authority, (d) Municipal Corporation etc. I M.I.D.C. in appropriate class as may be applicable of civil, valid on the date of submission.
 - ix. **Copy** of Income tax return FY 2024-25, i.e. AY 2025-26
 - x. **Copy** of pan Card.
 - xi. **Copy** of valid registration certificate under good and service tax Act 2017.
 - xii. **Copy** of details of satisfactorily completed a. should not less than 80 % for one similar work of estimated amount of the tender called, b. Two similar works whose cost wise work should not less than 50% of estimated amount of the tender called, c. Three similar works whose cost wise work Should not less than 40% estimated amount of the tender called in any Govt. or Semi Govt. organization only during last five years i.e., 2021-22, 2022-23, 2023-24, 2024-25, 2025-26 (In the proforma of Statement No. III). (As Per G.R. No.सकीर्ण /२०१९/प्र क्र ४७/इमास्ती -२, दि. २५/१०/२०१९)
6. SGST and CGST have been implemented by the respective Govt. with effect from 01/07/2017. So contractor must quote his rate keeping effect of GST in mind & no claims will be accepted by this office in connection to GST later.
 7. The successful bidder has to submit all the supported documents/ bills/ vouchers of the materials brought at site while claiming the bills.
 8. Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajnagar does not bind itself to accept the lowest or any such quotation and has the right to accept or reject whole or any part of tenders or a portion of the work without assigning any reasons. No correspondence in case of rejected tenders will be entertained. Incomplete quotations are liable to be rejected.

All questions, disputes or differences arising under and out of or in connection with the contract, if concluded, shall be referred to the sole arbitrator appointed by the Registrar, Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajnagar.

ANNEXURE - B

The building materials of product listed below shall be considered good materials and this tender should be based on the use of the materials of the following manufacturers. In case any of the following make material is not available, hence in such case, the other make can be allowed only on satisfactory evidence of non-availability of prescribed make. In both the cases the necessary tests need to be done only from the approved laboratories. The Executive Engineer & Architect may allow alternate make in case of any genuine problem.

Sr. No.	Material	Make
1	Cement	Brand of cement in 53 grade – BIRLA SUPER / BIRLA A-1 / BIRLA GOLD / ULTRATECH / AMBUJA/ COROMANDAL / J.K. Cement
2	Steel reinforcement	
	Integrated plant	TMT steel as per IS 1786
3	CRS steel	TISCO / Rashtriyaspat Nigam Ltd. / SAIL
4	G.I. item	Prakash-Surya / Swastik / Zenith
5	Plywood, Block board, flush door	Indian Plywood manufacturing Co. Ltd. / Anchor / Kitply / Swastik / Green Ply/ Century Ply
6	Glass	Ashish Glass / Modiguard / Saintgobain
7	Terrazzo Tiles	NITCO
8	Chequered Tiles	Sample approved by architect
9	Concrete Pavers block	Sample approved by architect
10	Glazed Tiles	Somany / Kajaria / Pedder / NITCO / Johnson & Johnson / Oasis / Asian
11	Ceramic	Kajaria / Pedder / Somany / NITCO / Johnson & Johnson / Oasis / Asian / Regency/Orient Bell
12	Vitrified tiles	NITCO / Kajaria / Pedder / Somany / Johnson & Johnson / Oasis / Asian / Spartex / Orient Bell
13	Laminates	Formica / Sunglass / Decolam / Royal Touch / Greenlam / Century
14	Paints	Berger / Jenson Nicholson / Nerolac / Asian Paint
15	Acrylic Emulsion Paint	Dulux / Berger / Asian Paint
16	Water Proof cement paint	Killick Nixon / Snowcem / Duracem
17	Aluminium Sections	INDAL / JINDAL
18	Pipes, waste water and vent pipes & fittings	SWR Supreme pipes / Ashirwad / Kisan / Kothari / Premier
19	G.I. Pipes	Zenith / Prakash / Surya / Swastic
20	Valves	Leader / Win / Elco
21	Rain water pipes	Supreme pipes / Ashirwad / Kisan / Kothari / Premier
22	Sanitary wares	Hindustan Sanitary Wares / 'CERA' / Parry Engineering & Electronic / Jonson & Jonson
23	Water supply fittings heavy type fittings	Jacquar / Hind ware/ L & K
24	PVC Doors, shutters, Tanks	SINTEX
25	Cement Concrete Pipes	Sample approved by architect
26	C.I. Soil pipe, waste water pipes, vent pipes fittings, Nahani trap	NECO of ISI 3989
31	Stainless steel sink	Nirali / Neelkanth
35	Galvanized Circular pipes & square / rectangle tubes	Zenith / Prakash-Surya / Swastic