Quotation
220

EPABX : (0240) 2403397 to 400
Off. Tele : (0240) 2403104 to 106
Registrar : (Offi.) (0240) 2403333
(Resi.) (0240) 2400203
Fax : (0240) 2403113 / 2403335
Web Site : www.bamu.net
E-mail : vc@bamu.net
E-mail : registrar@bamu.net

UNIVERSITY CAMPUS
Chh. Sambhajinagar-431004
(Maharashtra) INDIA

Ref. No. UE/TA/2026-27/ **Date: - 23/09/2026**

INVITATION OF QUOTATIONS IN TWO BIDS SYSTEMS

(Last Date for Submission 27.11.26 at 3.P.M.)

To,
M /s: _____

_____

Name of work: - Providing sliding gate at Main entrance gate of Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar.

The Terms & Conditions on the reverse should be read carefully and noted in order to comply.

SCHEDULE - B

Item No	Description of Item	Qty	Unit	Rate	Amount
1	Providing structural steel work of rectangular hollow steel section for steel trusses, other similar trussed items like purlin and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted/bolted/ welded connections and one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade complete. (I No 23.11)	0.560	MT	124729.50	69848.52
2	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc) (I.No.24.01)	0.88	Cum	6750.70	5940.62
3	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap /granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks,laying/pumping, compactionand roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete atch mix plant (Pan mixer) etc. complete. With fine aggregate	1.76	CUM	13464.54	23697.59
4	Dismantling the R.C.C. Work 1:2:4 and sorting out the materials such as steel etc. as directed and stacking them within the specified lead as directed etc.	3.51	Cum	1523.55	5347.66
	Estimated Amount				**104835**

JA JE Dy.Ez EE Registrar

TERMS AND CONDITIONS

1. The quotation should be addressed to Registrar, Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar & submitted in the office of Executive Engineer, Estate Section, Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar
2. The Contractor should provide following document at the time of submission of Quotation:-

(A) ENVELOPE NO. 1 DOCUMENTS)

The first envelope **"Envelope No.1"** shall contain the following documents.

i. **The Earnest Money Deposit** shall be paid via Demand Draft mode only. The DD should be enclosed. **(D.D. of Rs. 1100)**

ii. **Copy** of Certificate in Original or an attested copy as a registered contractor with (a) State P.W.D. (b) State Irrigation Dept. (c) Maharashtra Jeevan Pradhikaran Authority, (d) Municipal Corporation etc. I M.I.D.C. in appropriate class as may be applicable of civil, valid on the date of submission.

iii. **Copy** of Income tax return FY 2025-26, i.e. AY 2026-27

iv. **Copy** of pan Card.

v. **Copy** of valid registration certificate under good and service tax Act 2017.

vi. **Copy of** details of satisfactorily completed a. should not less than 80 % for one similar work of estimated amount of the tender called, b. Two similar works whose cost wise work should not less than 50% of estimated amount of the tender called, c. Three similar works whose cost wise work Should not less than 40% estimated amount of the tender called in any Govt. or Semi Govt. organization only during last five years i.e., 2021-22, 2022-23, 2023-24, 2024-25, 2025-26 (In the proforma of Statement No. III). (As Per G.R. No.सक्षेर्ण /२०१९/प्र क्र ४७/इमारती -२, दि. २५/१०/२०१९)

3. SGST and CGST have been implemented by the respective Govt. with effect from 01/07/2017. So contractor must quote his rate keeping effect of GST in mind & no claims will be accepted by this office in connection to GST later.
4. The successful bidder has to submit all the supported documents/ bills/ vouchers of the materials brought at site while claiming the bills.
5. Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar does not bind itself to accept the lowest or any such quotation and has the right to accept or reject whole or any part of tenders or a portion of the work without assigning any reasons. No correspondence in case of rejected tenders will be entertained. Incomplete quotations are liable to be rejected.

All questions, disputes or differences arising under and out of or in connection with the contract, if concluded, shall be referred to the sole arbitrator appointed by the Registrar, Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar.

ANNEXURE - B

The building materials of product listed below shall be considered good materials and this tender should be based on the use of the materials of the following manufacturers. In case any of the following make material is not available, hence in such case, the other make can be allowed only on satisfactory evidence of non-availability of prescribed make. In both the cases the necessary tests need to be done only from the approved laboratories. The Executive Engineer & Architect may allow alternate make in case of any genuine problem.

Sr. No.	Material	Make
1	Cement	Brand of cement in 53 grade – BIRLA SUPER / BIRLA A-1 / BIRLA GOLD / ULTRATECH / AMBUJA/ COROMANDAL / J.K. Cement
2	Steel reinforcement	
	Integrated plant	TMT steel as per IS 1786
3	CRS steel	TISCO / Rashtriyalspat Nigam Ltd. / SAIL
4	G.I. item	Prakash-Surya / Swastik / Zenith
5	Plywood, Block board, flush door	Indian Plywood manufacturing Co. Ltd. / Anchor / Kitply / Swastik / Green Ply/ Century Ply
6	Glass	Ashish Glass / Modiguard / Saintgobain
7	Terrazzo Tiles	NITCO
8	Chequred Tiles	Sample approved by architect
9	Concrete Pavers block	Sample approved by architect
10	Glazed Tiles	Somany / Kajaria / Pedder / NITCO / Johnson & Johnson / Oasis / Asian
11	Ceramic	Kajaria / Pedder / Somany / NITCO / Johnson & Johnson / Oasis / Asian / Regency/Orient Bell
12	Vitrified tiles	NITCO / Kajaria / Pedder / Somany / Johnson & Johnson / Oasis / Asian / Spartex / Orient Bell
13	Laminates	Formica / Sunglass / Decolam / Royal Touch / Greenlam / Century
14	Paints	Berger / Jenson Nicholson / Nerolac / Asian Paint
15	Acrylic Emulsion Paint	Dulux / Berger / Asian Paint
16	Water Proof cement paint	Killick Nixon / Snowcem / Duracem
17	Aluminium Sections	INDAL / JINDAL
18	Pipes, waste water and vent pipes & fittings	SWR Supreme pipes / Ashirwad / Kisan / Kothari / Premier
19	G.I. Pipes	Zenith / Prakash / Surya / Swastic
20	Valves	Leader / Win / Elco
21	Rain water pipes	Supreme pipes / Ashirwad / Kisan / Kothari / Premier
22	Sanitary wares	Hindustan Sanitary Wares / 'CERA' / Parry Engineering & Electronic / Jonson & Jonson
23	Water supply fittings heavy type fittings	Jacquar / Hind ware/ L & K
24	PVC Doors, shutters, Tanks	SINTEX
25	Cement Concrete Pipes	Sample approved by architect
26	C.I. Soil pipe, waste water pipes, vent pipes fittings, Nahani trap	NECO of ISI 3989
31	Stainless steel sink	Nirali / Neelkanth
35	Galvanized Circular pipes & square / rectangle tubes	Zenith / Prakash-Surya / Swastic