

DR. BABASAHEB AMBEDKAR MARATHWADA UNIVERSITY,
CHHATRAPATI SAMBHAJINGAR- 431 004, Maharashtra State (India)

NAAC - Accredited A+

EPABX :- (0240) 2403397 to 400
Off. Tele :- (0240) 2403104 to 106
Registrar :- (Offi.) (0240) 2403333
(Resi.) (0240) 2400203
Fax :- (0240) 2403113 / 2403335
Web Site :- www.bamu.net
E-mail :- vc@bamu.net
E-mail :- registrar@bamu.net



UNIVERSITY CAMPUS
CHH. SAMBHAJINAGAR-431004
(Maharashtra) INDIA

Ref. No. UE/TA/2026-27/ 541

Date: 15/07/2026

Corrigendum

Subject : 2nd Extension of Time for submission of Quotation.
Name of Work : Construction of UCR Compound wall at Gut No. 45.

Quotations were invited for the work of **Construction of UCR Compound wall at Gut No. 45** and the same was also published on the University website.

Due to poor response received for the above quotation, the last date for submission of quotations has been extended up to 3:00 PM on 18/07/2026.

T.A.

J.E.

Dy.E.

Executive Engineer

0/2

EPABX : (0240) 2403397 to 400
 Off. Tele : (0240) 2403104 to 106
 Registrar : (Offi.) (0240) 2403333
 (Resi.) (0240) 2400203
 Fax : (0240) 2403113 / 2403335
 Web Site : www.bamu.net
 E-mail : vc@bamu.net
 E-mail : registrar@bamu.net



Quotation
 194
 UNIVERSITY CAMPUS
 Chh. Sambhajinagar-431004
 (Maharashtra) INDIA

Ref. No. UE/TA/2026-27/ 470

Date: - 23/06/2026

01/07/

INVITATION OF QUOTATIONS IN TWO BIDS SYSTEMS

(Last Date for Submission)

08/07/2026, 3.00 PM

To: _____
 M/s: _____
 Time Extension Last Date of Submission 13/07/2026, 3:00 PM
 2nd Time Extension Last Date of Submission 18/07/2026, 3:00 PM

Name of work: - Construction of UCR Compound wall at Gut No. 45 in the premises of Dr. Babasaheb Ambedkar Marathwada University, Chhatrapati Sambhajinagar.

The Terms & Conditions on the reverse should be read carefully and noted in order to comply.


SCHEDULE - B


Item No.	Description of Items	Qty.	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Mechanical Means	16.20	Cu.M	217.35	3521.07
2	Excavation for foundation in hard murum including removing the excavated material up to distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Means	16.20	Cu.M	238.35	3861.27
3	Excavation for foundation in hard murum and boulders including removing the excavated material upto a distance 50 metres, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5m.) By Mechanical Means	8.10	Cu.M	264.60	2143.26
4	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	3.24	Cu.M	1991.55	6452.62
5	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.62	Cu.M	6734.05	10909.16

7	Providing uncoursed rubble masonry of trap / granite / quartzite / gneiss stones in cement mortar 1:6 in superstructure including racking out joints when plastering is to be done / striking joints when no plastering is to be done on inside watering and scaffolding etc.complete.	32.40	Cu.M	6633.76	214933.82
8	Providing flush grooved pointing with cement mortar 1:3 for stone masonry work including scaffolding and curing etc. complete.	86.40	Sq.M	193.67	16733.09
9	Providing and laying Cast in situ/Ready Mix cement concrete M-15 of trap/ granite/quartzite/gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/ steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) With fine aggregate (Crushed sand VSI Grade).	2.03	Cu.M	7246.25	14709.88
10	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	18.90	Sq.M	699.22	13215.26
11	Royalty against extraction of material such as metal, sand, murum, rubble, etc. for construction work.				
	Royalty of Sand	13.88	Cu.M	237.37	3294.10
	Royalty of Other Material	44.15	Cu.M	216.18	9545.10
	ESTIMATED AMOUNT				299318.64
	Say				299319


J.A.


E.M.


Dy. E.


E. E.


Registrar


J.E.